HUNSUR SUB-DIVISION.

NOTICE.

It is hereby notified that an unserviceable Swiss cottage tent of the Hunsur Sub-Division Office will be sold by the undersigned by public auction in the compound of the Public Offices, Mysore, from 9 to 11 A.M. on the 15th December 1906.

The purchase money should be paid down at once. The sale is subject to the confirmation of the Deputy Commissioner.

A. SUBRAMANYA IYER,
Assistant Commissioner.

CHITALDRUG DIVISION.

Dated 1st December 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 12 noon of 17th December 1906, for constructing an Anglo-Vernacular School at Challakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an Anglo-Vernacular School at Challakere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the probable cost of constructing Anglo-Vernacular School at Challakere.—

No.	Items of work	Per	Quantity.
1	Earthwork excavation hard and gravelly soil and filling basement ...	C. yds.	177
2	Burnt stone in mortar, foundation	C. ft.	2,600
3	Do do basement	„	1,233
4	Burnt brick in chunam, superstructure	„	5,208
5	Do do arch work	„	166
6	Burnt stone slabs (4" to 6") thick dressed	Sqr. ft.	321
7	Chunam plastering	Sqrs.	76·94
8	Pointing basement	„	2·59
9	White and color washing	„	76·94
10	Teakwood work	C. ft.	207·48
11	Roofing with 1st class Mangalore tiles, etc., complete	Sqrs.	25·68
12	Ridge tiles set in mortar	R. ft.	133
13	Brick in chunam cornice work	„	302
14	Masonry finial, large	Each	4
15	Zinc sheet for the valley	S. ft.,	90
16	Teakwood doors pannelled	„	180
17	Do windows inside glazed and pannelled outside	„	298
18	Wood oiling	Sqrs.	22·00
19	Chacolate painting doors and windows	„	9·00
20	Flooring with Cuddapah slabs (1½ to 2" thick) over 3" concrete and cement pointing	„	13·99
21	Ventilating tiles	Each	64
22	Finial over porch	„	2
23	Sun shades	„	20
24	Clearing site and levelling ground	Lump sum.	

Dated 6th December 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 23rd December 1906, for restoring the Sujical Tank, Registered No. 327, Hosdurga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Sujical Tank, Registered No. 327, Hosdurga Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of restoring Sujical Tank, Registered No. 327, Hosdurga Taluk.

No.	Items of work	Par	Bund	Sluices	Weir No.	Weir N. II	Weir No. III	Total
			Quantity	Quantity	Quantity	Quantity	Quantity	Quantity
1	Earthwork with watering and tamping	C. yd.	12,625	...	...	...	...	12,625
2	Resetting old stone work with new jelly	,,	390	...	...	...	...	390
3	New stone work	,,	1,028	...	...	...	...	1,028
4	Turfing	S. yd.	15,315	...	...	...	...	15,315
5	Registered No. stone... ...	Each	1	..	...	...	..	1
6	B. M. stones	,,	2	...	...	...	...	2
7	Removing and refixing grade stones	,,	37	...	...	...	...	37
8	Bund width stones	,,	37	..	...	...	...	37
9	Gauge stone, complete ...	,,	1	...	...	...	...	1
10	Clearing jungle	L. S.	Rs.	..	...	...	...	Rs.
11	Re-building sluices (60+60+50) ...	R. ft.	...	170	...	...	...	...
12	Earthwork excavating foundation and benching trench in rock ...	L. S.	...	...	Rs.	30	Rs.	30
13	Brick in surki mortar ...	C. ft.	...	...	1,280	351	380	2,011
14	Surki plastering	Sqr.	...	...	9·53	4·30	3·70	17·53
15	Burnt stone slabs, 4" thick ...	S. ft.	...	...	356	71	122	549
16	Old stone work	C. yd.	...	...	50	25	30	105
17	Filling apron with new jelly ...	L. S.	...	...	Rs.	Rs.	....	Rs.
18	New stone work	C. yd.	...	...	...	30	90	120
19	Burnt stone in surki mortar ...	C. ft.	...		...	122	369	491
20	Pointing with surki mortar ...	Sqr.	...	...	...	·81	2·46	3·27

K. PRAHLADA RAO,
Executive Engineer.